

DEVELOPMENT EXPENSES ELIGIBLE FOR REIMBURSEMENT OF PROPERTY TAXES OF CERTIFIED FOREST PRODUCERS

Development expenses for the technical component include planning, monitoring and operational supervision costs.

Development expenses for the execution component include implementation costs.

A silvicultural treatment must be applied in compliance with the scientific foundations presented in the Guide sylvicole du Québec.

A silvicultural treatment is part of a silvicultural scenario to be applied to a stand or combination of stands during a given period based on management objectives.

1. Return to production

1.1 Site preparation

Definition

A silvicultural treatment that involves working the forest soil to make the physical environment suitable for germination or for the survival and the growth of seedlings of a desired species. Site preparation must create a sufficient number of microsites suitable for natural or artificial regeneration.

Description of eligible silvicultural site preparation activities

- 1.1.1 Mechanical site clearing: a silvicultural treatment that involves windrowing or piling logging residue in order to facilitate replanting, scarification or stand tending.
- 1.1.2 Shear-blading with a shear-blade-equipped tractor: brush-cutting and windrowing in a single operation.
- 1.1.3 Bush clearing and site clearing: elimination and removal of brush and non-merchantable timber.
 - 1.1.3.1 High competition: an operation carried out where the coverage of brush two metres or more in height exceeds 50%.
 - 1.1.3.2 Low competition: an operation carried out where the coverage of brush one metre or more in height exceeds 25%.
- 1.1.4 Chipping: the removal and chipping of brush and non-merchantable timber in a single operation.
- 1.1.5 Forest harrowing: brush removal and soil scarification using a forest harrow.
- 1.1.6 Agricultural ploughing and harrowing: loosening of the soil using a plough and harrow to facilitate the planting of seedlings.
- 1.1.7 Scarification: a silvicultural treatment that involves disturbing the humus layer and low-growing competing vegetation to expose and loosen the mineral soil and mix it with organic matter.
 - 1.1.7.1 Light scarification: TTS-type disc trenchers.
 - 1.1.7.2 Medium scarification: TTS-type trenchers with hydraulic discs, Donaren, Equisyl, etc.
 - 1.1.7.3 Manual scarification: manual tools.
- 1.1.8 Salvage, bush clearing and site clearing: the harvesting of all mature merchantable timber or deteriorating timber in a low-value stand followed by bush clearing and mechanical site clearing.
- 1.1.9 Site clearing with a “stone-fork” excavator: a silvicultural treatment that involves windrowing or piling logging residue in order to facilitate replanting.
- 1.1.10 Mounding scarification: an operation involving the mounding of soil using an excavator or feller to create at least 800 microsites per hectare in order to perform intensive silviculture or reforestation with hardwood, white pine or red pine.
- 1.1.11 Forest ploughing and harrowing: brush removal and loosening of the soil using a forest plough and harrow.

Value of site preparation treatments

TREATMENT	EXECUTION		TECHNICAL		TOTAL VALUE	UNIT
	VALUE	FAMILY OF DEVELOPMENT EXPENSES	VALUE	FAMILY OF DEVELOPMENT EXPENSES		
Mechanical site clearing	\$1,004	PtRMe	\$240	Technical work	\$1,244	hectare (ha)
Shear-blading with a shear-blade-equipped tractor	\$1,680	PtRMe	\$240	Technical work	\$1,920	ha
Bush clearing and site clearing – high competition	\$1,871	PtRMe	\$240	Technical work	\$2,111	ha
Bush clearing and site clearing – low competition	\$628	PtRMe	\$240	Technical work	\$868	ha
Chipping	\$1,872	PtRMe	\$240	Technical work	\$2,112	ha
Forest harrowing – single pass	\$529	PtRMe	\$240	Technical work	\$769	ha
Forest harrowing – double pass	\$906	PtRMe	\$240	Technical work	\$1,146	ha
Agricultural ploughing and harrowing	\$629	PtRMe	\$240	Technical work	\$869	ha
Light scarification	\$280	PtRMe	\$240	Technical work	\$520	ha
Medium scarification	\$430	PtRMe	\$240	Technical work	\$670	ha
Manual scarification	\$362	PtRMa	\$154	Technical work	\$516	1,000 microsites
Salvage, bush clearing and site clearing	\$1,303	PtRMe	\$511	Technical work	\$1,814	ha
Site clearing with a “stone-fork” excavator	\$1,596	PtRMe	\$240	Technical work	\$1,836	ha
Mounding scarification	\$911	PtRMe	\$355	Technical work	\$1,266	ha
Forest ploughing and harrowing	\$1,578	PtRMe	\$616	Technical work	\$2,194	ha

1.2 Planting

Definition

An operation involving burying the root system of artificial seedlings in a mineral soil or a mixture of mineral and organic soil.

Description of eligible silvicultural planting treatments

- 1.2.1 Planting: an artificial regeneration treatment involving placing seeds or seedlings in the ground, with regular spacing, to create a stand.
- 1.2.2 Infill planting in plantations or naturally-regenerated areas: an artificial regeneration treatment that involves planting trees of a commercial species to fill gaps in areas where the regeneration, whether natural or artificial, has not achieved a suitable density or distribution coefficient. Infill planting takes place in a natural stand or a plantation containing trees of similar dimension to the seedling in order to achieve full stocking of the area.
- 1.2.3 Enrichment planting: an artificial regeneration treatment that involves planting trees in a stand to introduce or re-introduce a species that is in decline or has greater value, or to increase the abundance of that species. Enrichment planting may take place in the understorey of a stand to maintain or improve biodiversity or increase the value of the stand.

Value of planting treatments

TREATMENT	EXECUTION		TECHNICAL		TOTAL VALUE	UNIT
	VALUE	FAMILY OF DEVELOPMENT EXPENSES	VALUE	FAMILY OF DEVELOPMENT EXPENSES		
Mechanized planting – mechanical planter	\$1,790	PtRMe	\$274	Technical work	\$2,064	1,000 seedlings
Manual planting - Bare-root, large size	\$550	PtRMa	\$289	Technical work	\$839	1,000 seedlings
Manual planting - containers of 50 to 109 cubic centimetres (cc)	\$214	PtRMa	\$265	Technical work	\$479	1,000 seedlings
Manual planting - containers of 110 to 199 cc	\$290	PtRMa	\$271	Technical work	\$561	1,000 seedlings
Manual planting - containers of 200 to 299 cc	\$434	PtRMa	\$285	Technical work	\$719	1,000 seedlings
Manual planting - containers of 300 cc and over	\$490	PtRMa	\$304	Technical work	\$794	1,000 seedlings
Manual planting - containers of 300 cc and over (15 cells)	\$555	PtRMa	\$304	Technical work	\$859	1,000 seedlings
Manual planting - hybrid poplar	\$780	PtRMa	\$304	Technical work	\$1,084	1,000 seedlings
Infill/enrichment planting - Bare-root, large size	\$668	PtRMa	\$289	Technical work	\$957	1,000 seedlings
Infill/enrichment planting - containers of 50 to 109 cc	\$346	PtRMa	\$265	Technical work	\$611	1,000 seedlings
Infill/enrichment planting - containers of 110 to 199 cc	\$408	PtRMa	\$271	Technical work	\$679	1,000 seedlings
Infill/enrichment planting - containers of 200 to 299 cc	\$556	PtRMa	\$285	Technical work	\$841	1,000 seedlings
Infill/enrichment planting - containers of 300 cc and over	\$584	PtRMa	\$304	Technical work	\$888	1,000 seedlings
Infill/enrichment planting - containers of 300 cc and over (15 cells)	\$660	PtRMa	\$304	Technical work	\$964	1,000 seedlings
Infill/enrichment planting - hybrid poplar	\$780	PtRMa	\$304	Technical work	\$1,084	1,000 seedlings

2. Tending of regeneration

Definition

A silvicultural tending treatment that involves eliminating competing vegetation, mainly using mechanical or manual methods, to release regeneration of the desired species or to create an environment suitable for the establishment of regeneration.

Description of eligible silvicultural treatments for the tending of regeneration

- 2.1 Cleaning (1st, 2nd, 3rd): an operation that involves cutting back competing trees and shrubs.
- 2.2 Weeding: an operation that involves controlling competing herbaceous vegetation, either by mowing or harrowing or by straightening seedlings.
- 2.3 Mulching: an operation that involves controlling competing trees and shrubs by mulching
- 2.4 Fertilization and amendment: a treatment that involves the application of chemical or organic fertilizers to improve timber production in stands of quick-growth species and in maple stands used for forestry or syrup production under a silvicultural diagnosis by a forest engineer.
- 2.5 Artificial pruning: a silvicultural tending treatment that involves systematically removing dead or living branches from the lower part of a tree stem to produce knot-free timber. The treatment aims to increase the value of the butt log in the production of high-quality timber for sawing or rotary cutting.
- 2.6 Phytosanitary pruning of white pine and red pine: a silvicultural tending treatment that involves removing parts of a tree (generally branches or twigs) that are dead, damaged or affected by pathogens. This silvicultural treatment aims to prevent the spread of parasites and pathogens.
- 2.7 Protective treatment: a treatment to combat insects, disease or animals to stop their spread or minimize damage to trees.

Value of eligible treatments for the tending of regeneration

TREATMENT	EXECUTION		TECHNICAL		TOTAL VALUE	UNIT
	VALUE	FAMILY OF DEVELOPMENT EXPENSES	VALUE	FAMILY OF DEVELOPMENT EXPENSES		
Cleaning (1 st , 2 nd , 3 rd)	\$1,720	E. P.	\$606	Technical work	\$2,326	hectare (ha)
Weeding	\$370	E. P.	\$606	Technical work	\$976	ha
Mulching	\$1,253	PtRMe	\$490	Technical work	\$1,743	ha
Fertilization and amendment	\$683	PtRMe	\$266	Technical work	\$949	ha
Artificial pruning	\$521	E. P.	\$222	Technical work	\$743	ha
Phytosanitary pruning of white pine and red pine	\$952	E. P.	\$596	Technical work	\$1,548	ha
Protective treatment	\$561	PtRMa	\$239	Technical work	\$800	ha

3. Stand tending

3.1 Precommercial thinning

Definition

A silvicultural tending treatment that involves cutting trees with non-merchantable dimensions to reduce the competition for final crop trees and improve their growth. Precommercial thinning aims mainly to reduce competition between trees of a desired species.

Description of eligible silvicultural stand tending treatments

- 3.1.1 Systematic precommercial thinning: a variant characterized by the removal of trees and shrubs that compete with the selected crop trees, using a defined spacing that ensures that the crop trees make up the entire cover in the stand.
- 3.1.2 Precommercial thinning with light opening: a variant characterized by the removal of competing trees and shrubs (competing vegetation) within a defined radius around a number of selected crop trees to ensure that they form a predominant portion of the stand. Precommercial thinning by light opening retains the trainer (filler) trees.

Value of stand tending treatments

TREATMENT	EXECUTION		TECHNICAL		TOTAL VALUE	UNIT
	VALUE	FAMILY OF DEVELOPMENT EXPENSES	VALUE	FAMILY OF DEVELOPMENT EXPENSES		
Systematic precommercial thinning–softwood and mixed stands: 8 000 to 15 000 stems/hectare (ha)	\$1,339	Stand tending	\$596	Technical work	\$1,935	hectare (ha)
Systematic precommercial thinning – softwood and mixed stands: 15 000 stems/ha and over	\$1,789	Stand tending	\$596	Technical work	\$2,385	ha
Systematic precommercial thinning – poplar	\$968	Stand tending	\$414	Technical work	\$1,382	ha
Precommercial thinning with light opening and marking	\$1,235	Stand tending	\$889	Technical work	\$2,124	ha

4 Commercial treatments

Definition

All silvicultural treatments involving the partial or total harvesting of the merchantable trees in a stand.

Description of eligible commercial silvicultural treatments

- 4.1 Commercial thinning: silvicultural tending treatment that involves harvesting some merchantable stems in an even-aged stand prior to maturity.
- 4.2 Shelterwood cutting: a silvicultural treatment that involves harvesting the stand in a series of partial cuts spaced at about one-fifth of the rotation, to establish one or more regeneration cohorts under the protection of mature forest cover containing seed trees.
- 4.3 Selection cutting: the periodic harvesting of trees in an uneven-aged or “gardened” stand to promote regeneration.
- 4.4 Salvage cutting: an operation that involves harvesting merchantable stems in a deteriorating stand, to safeguard or replace the regeneration of commercial species damaged by windthrow, insect epidemic, ice storm or fire.
- 4.5 Technical assistance for timber development: assistance provided to a forest producer to plan silvicultural work and technical advice on the implementation of treatments, which may cover silvicultural prescriptions, performance reports, marking, permit applications, compliance with municipal by-laws and environmental regulations, and timber marketing.
- 4.6 Marking: an operation that involves marking trees, generally using spray paint, either to be felled (negative marking) or to be left standing (positive marking) during a planned selection cut. Marking may be used for commercial thinning, shelterwood cutting, selection cutting, partial salvage cutting, sanitation cutting or improvement cutting.
- 4.7 Succession cutting: the harvesting of overstorey trees while retaining the regeneration of desired species established in the understorey, in order to improve stand composition.
- 4.8 Sanitation cutting: the removal of trees killed or weakened by diseases or insects to avoid their spread to the remainder of the stand.
- 4.9 Improvement cutting: the removal of undesired species or poorly-formed trees in a stand that is beyond the sapling stage, in order to improve stand composition, structure and condition.

Value of commercial treatments

TREATMENT	EXECUTION		TECHNICAL		TOTAL VALUE	UNIT
	VALUE	FAMILY OF DEVELOPMENT EXPENSES	VALUE	FAMILY OF DEVELOPMENT EXPENSES		
First commercial thinning: softwoods - fir, spruce, jackpine and larch (FSJL) 9 to 15 centimetres (cm) diameter at breast height (DBH) -mechanized	\$1,286	T. C.	\$554	Technical work	\$1,840	hectare (ha)
First commercial thinning: softwoods (FSJL), 9 to 15 cm DBH - manual	\$1,838	T. C.	\$554	Technical work	\$2,392	ha
First commercial thinning: softwoods (FSJL), 15.1 to 19 cm DBH - mechanized	\$1,053	T. C.	\$554	Technical work	\$1,607	ha
First commercial thinning: softwoods (FSJL), 15.1 to 19 cm DBH - manual	\$1,506	T. C.	\$554	Technical work	\$2,060	ha
Second commercial thinning: softwood (FSJL) plantations – mechanized	\$715	T. C.	\$554	Technical work	\$1,269	ha
Second commercial thinning: softwood (FSJL) plantations - manual	\$1,022	T. C.	\$554	Technical work	\$1,576	ha
First commercial thinning: white pine and red pine plantations – mechanized	\$1,093	T. C.	\$554	Technical work	\$1,647	ha
First commercial thinning: white pine and red pine plantations - manual	\$1,562	T. C.	\$554	Technical work	\$2,116	ha
Second commercial thinning: white pine and red pine plantations – mechanized	\$611	T. C.	\$554	Technical work	\$1,165	ha
Second commercial thinning: white pine and red pine plantations – manual	\$874	T. C.	\$554	Technical work	\$1,428	ha

Commercial thinning, natural stands – hardwoods and other softwoods – mechanized	\$959	T. C.	\$554	Technical work	\$1,513	ha
Commercial thinning, natural stands – hardwoods and other softwoods - manual	\$1,372	T. C.	\$554	Technical work	\$1,926	ha
Shelterwood cutting - softwoods (FSJL) - mechanized	\$705	T. C.	\$554	Technical work	\$1,259	ha
Shelterwood cutting - softwoods (FSJL) - manual	\$1,008	T. C.	\$554	Technical work	\$1,562	ha
Shelterwood cutting – shade-tolerant hardwoods and other softwoods - mechanized	\$1,037	T. C.	\$554	Technical work	\$1,591	ha
Shelterwood cutting - shade-tolerant hardwoods and other softwoods - manual	\$1,484	T. C.	\$554	Technical work	\$2,038	ha
Selection cutting - softwoods (FSJL) - mechanized	\$930	T. C.	\$554	Technical work	\$1,484	ha
Selection cutting - softwoods (FSJL) - manual	\$1,328	T. C.	\$554	Technical work	\$1,882	ha
Selection cutting – shade-tolerant hardwoods and other softwoods - mechanized	\$928	T. C.	\$554	Technical work	\$1,482	ha
Selection cutting - shade-tolerant hardwoods and other softwoods - manual	\$1,327	T. C.	\$554	Technical work	\$1,881	ha
Salvage cutting - partial, manual	\$1,309	T. C.	\$554	Technical work	\$1,863	ha
Salvage cutting - partial, mechanized	\$915	T. C.	\$554	Technical work	\$1,469	ha
Salvage cutting - total, manual	\$561	T. C.	\$334	Technical work	\$895	ha
Salvage cutting - total, mechanized	\$393	T. C.	\$334	Technical work	\$727	ha
Technical assistance for timber development	\$0	N/A	\$334	Technical work	\$334	ha
Marking, hardwoods ¹	\$0	N/A	\$188	M.	\$188	ha
Marking, softwoods ¹	\$0	N/A	\$216	M.	\$216	ha
Succession cutting	\$993	T. C.	\$359	Technical work	\$1,352	ha
Sanitation cutting	\$918	T. C.	\$332	Technical work	\$1,250	ha
Improvement cutting	\$1,230	T. C.	\$446	Technical work	\$1,676	ha

¹The marking rate applies only to eligible commercial treatments

5 Other activities

Description of other eligible activities

- 5.1 Forest roads: the construction or improvement of access roads, bridges and culverts to facilitate forest operations.
- 5.2 Forest development plan: the drafting of an information and planning tool by a forest engineer for benefit of a forest producer, in order to protect and develop a forest property.
- 5.3 Supplemental forest development plan: the inclusion of extra information in the forest development plan concerning the presence of at least one sensitive element on a forested property, as confirmed by cartographic data from a recognized source or the gathering of ecological data. The eligible sensitive elements are:
 - 5.3.1 Wetlands;
 - 5.3.2 Occurrences or potential habitats of a designated threatened or vulnerable species or a species likely to be designated threatened or vulnerable;
 - 5.3.3 Exceptional forest ecosystems;
 - 5.3.4 Sensitive forest ecosystems, or forest ecosystems that are vulnerable to climate change, as well as ecological hubs and corridors.

The inclusion of sensitive elements must be supported by an ecological description and mitigation measures in the silvicultural treatments proposed in the forest development plan.

- 5.4 Delimitation of sensitive areas: on-site delimitation of a sensitive element described in point 5.3 for conservation purposes, prior to the implementation of a planned forest management activity.
- 5.5 Multi-resource component provided for in the forest development plan: the drafting of an information tool for potential multi-resources based on a multi-resource data collection; the component is added to the forest development plan, as it is described in point 5.2 of this Schedule.
- 5.6 Forest-fauna work: forest development activities provided for in this Regulation if they are implemented to conserve or improve a wildlife habitat. The work results from an analysis of the wildlife potential and is provided for in the forest development plan or the silvicultural prescription of a forest engineer. The value of the development expense for the technical component or execution component is increased by 10%.
- 5.7 Advisory visit: an advisory visit, including an on-site analysis to follow up on the forest development plan with the owner, or to advise the owner on the implementation of development work on the owner's forested land. The visit must be conducted under the responsibility and supervision of a forest engineer. Maximum number of visits per forest development plan per year: 1.
- 5.8 Forest certification: work to obtain or maintain forest certification under a recognized group program.

Value of other activities

TREATMENT	EXECUTION		TECHNICAL		TOTAL VALUE	UNIT
	VALUE	FAMILY OF DEVELOPMENT EXPENSES	VALUE	FAMILY OF DEVELOPMENT EXPENSES		
Construction of access roads ¹	\$2,584	T. C.	\$934	Technical work	\$3,518	Kilometre (km)
Improvement of access roads ¹	\$1,230	T. C.	\$446	Technical work	\$1,676	km
Construction of bridges or culverts ¹	\$1,448	T. C.	\$523	Technical work	\$1,971	One bridge or one culvert
Improvement of bridges or culverts ¹	\$196	T. C.	\$72	Technical work	\$268	One bridge or one culvert
Forest development plan (4 to 10 hectares (ha)) ¹	\$0	N/A	\$593	Technical work	\$593	One forest development plan
Forest development plan (11 to 50 ha) ¹	\$0	N/A	\$652	Technical work	\$652	One forest development plan
Forest development plan (51 to 100 ha) ¹	\$0	N/A	\$852	Technical work	\$852	One forest development plan
Forest development plan (101 to 799 ha) ¹	\$0	N/A	\$1,186	Technical work	\$1,186	One forest development plan
Forest development plan (800 ha and over) ¹	\$0	N/A	\$1,423	Technical work	\$1,423	One forest development plan
Supplemental forest development plan ¹	\$0	N/A	\$279	Technical work	\$279	Per sensitive element
Delimitation of sensitive areas	\$0	N/A	\$183	Technical work	\$183	ha
Multi-resource component provided for in the forest development plan ¹	\$0	N/A	\$238	Technical work	\$238	Per forest development plan
Forest-fauna work	\$0	N/A	\$0	N/A	10%	N/A
Advisory visit	\$0	N/A	\$415	Technical work	\$415	One visit
Forest certification	\$0	N/A	\$3	Technical work	\$3	ha

¹Upon presentation of eligible invoices and proof of payment by the producer (to be attached to the forest engineer's report for validation), the value of the expense indicated in the above table may correspond to the total of the amount of the validated invoices, up to twice the indicated value.